



MINISTRY OF PLANTATION



STATE MINISTRY OF COMPANY ESTATE REFORMS,  
TEA AND RUBBER ESTATE RELATED CROPS CULTIVATION  
AND FACTORIES MODERNIZATION AND TEA AND RUBBER  
EXPORT PROMOTION

**RUBBER RESEARCH INSTITUTE OF SRI LANKA**  
**PROCUREMENT NOTICE**

RRISL/PRO/RT&DD/R&D/2022 (28)

Registered Post

**Construction of Concrete Floor**

Bids are hereby invited from registered contractors (Building Construction – CIDA C9 and C8 Colombo District) of Construction Industry Development Authority with validity for year 2022.

Sealed bids furnishing the information required **in the attached standard Bidding document (Annexure I) filling the all empty cages** should be send to the Chairman, Department Procurement Committee (Minor), Rubber Research Institute of Sri Lanka, Dartonfield, Agalawatta under registered cover or should be placed into the box available in the Account Department (Procurement unit), Dartonfield, Agalawatte. **Otherwise they will be rejected.**

The envelope containing the Bid should bear the words “**Construction of Concrete Floor**” in its top left corner. Bids close at **2.30 pm** on **10.06.2022** and they will be opened immediately after the closing time on the same day at Dartonfield, Agalawatte. The decision of the Procurement Committee will be final and definite. Bidders or their authorized representatives will be permitted to be present for the event of opening of bids.

**Chairman**  
**Departmental Procurement Committee (Minor)**  
**Rubber Research Institute of Sri Lanka**  
**Dartonfield, Agalawatte**  
**20.05.2022**

**CONSTRUCTION OF CONCRETE FLOOR  
RUBBER RESEARCH INSTITUTE, DARTONFIELD, AGALAWATTA**

<b>Bill Item</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
<b>1</b>	<b>Preliminaries</b>				
1.1	Contractor's Mobilization	item	1		
1.2	Site Clearing and debris away	Item	1		
<b>2</b>	<b>Demolishing Work &amp; Earth Works</b>				
2.1	Manual Excavation over site to reduce level in any material (except rock requiring blasting) including depositing and levelling as directed up to a distance not exceeding 30'-0". Appro 3 cube	Cube	1		
2.2	Demolishing 9" thick brick walls stacking brick and clearing debris away	Cube	2		
2.3	Demolishing reinforced cement concrete	Cube	0.5		
2.4	River Sand supplying spreading laying and compacting in foundation trenches where measured on compacted volume.	Cube	1.25		
2.5	Supply and fixing Approved Earth spreading, leveling watering and compaction manually using standard cast iron stamper or equivalent and filling in 150 mm thick layers	Cube	4		
<b>3</b>	<b>Concrete</b>				
3.1	Volume Batched Grade 25 concrete prepared at site using mixer and vibrator in ground floor.	Cube	1.20		
3.2	Shuttering for sides of plinth beams, ground beams on top of foundation including dismantling in 15mm thick plywood	Sqr	0.50		
3.3	Tor steel reinforcement to slabs, beams, lintols, columns, footings etc.. bent to shape, laid in position and tied with 16 B.W.G. Anear binding wire in Ground floor	kg	150.00		

3.4	Gauge 750 polythene damp proof membrane with 6" laps laid under floors	Sqr	2.00		
3.5	Supplying and fixing 12 mm thick 150 mm height polystyrene board for edges	ft	56.00		
<b>4</b>	<b>Anti- termite treament</b>				
4.1	Anti-termite treatment for the post construction (Existing building ) with applying Biflexthrine 10Tc (Biflex ) or approved equivalent as per manufacturer's standards of application with 5 years warranty on application (Measured on plinth area).	Sqr	12.00		
<b>5</b>	<b>Colour Washing and Painting</b>				-
5.1	Applying two coats of skim coat ( Not exceeding 3 mm thick) to walls inc. preparation surface	Sqr	2.00		
5.2	Painting walls with two coats of emulsion paint including preparing surface	Sqr	2.00		
6	Provisional Sum for additional work	P/S	1.00	50,000.00	50,000.00
<b>TOTAL AMOUNT</b>					

Total bid amount in words:.....

.....

Bidder's Name:.....

Address:.....

.....

Telephone Number: .....

E-mail Address: .....

.....  
Date

.....  
Signature

**OFFICIAL SEAL**